

**INITIAL PHASE:**  
CONTRACTOR TO INSTALL PERIMETER FENCE PRIOR TO ALL LAND DISTURBANCE ACTIVITIES. ALL INITIAL PERIMETER FENCE SHALL BE REMOVED CONCURRENTLY WITH INTERMEDIATE MEASURES.

**INTERMEDIATE PHASE:**  
EROSION MEASURES SHALL CONSIST OF ALL BMP'S SHOWN IN THESE PLANS EXCEPT FOR Ds3. ALL DEVICES INSTALLED DURING THIS PHASE SHALL REMAIN UNTIL FINAL GRADING HAS BEEN ACHIEVED AND PERMANENT MEASURES INSTALLED.

**FINAL PHASE:**  
SHALL CONSIST OF PERMANENT GRASSING, STONE DUMPED RIP RAP FOR OUTLET PROTECTION, AND PERMANENT DITCH PROTECTION. CONTRACTOR IS TO ENSURE THAT ALL GRASS PLANTED HAS STARTED TO GROW BEFORE REMOVING TEMPORARY EROSION MEASURES.

SEE SHEET 13-02  
MATCH LINE STA. 14+40

MATCH LINE STA. 19+40  
SEE SHEET 13-04

EASEMENT FOR THE CONSTRUCTION AND MAINTENANCE OF SLOPES  
CENTERLINE INTERSECTION  
SR 124  
STA 15+65.29  
HARRISON STREET  
STA 20+00.00


EASEMENT FOR THE CONSTRUCTION AND MAINTENANCE OF SLOPES

- Ds1 ALL DISTURBED AREAS WITH IN 14 DAYS OF DISTURBANCE (TYP)
- Ds2
- Ds3 PERMANENT GRASSING

LIMIT OF CONSTRUCTION  
STA 18+66.58  
MATCH EXISTING

GSWCC LEVEL 1 DESIGN PROFESSIONAL NO. 0000018858  
*[Signature]*  
GEORGIA LICENSED PROFESSIONAL  
DATE 2-25-10

CENTERLINE INTERSECTION  
STA 15+65.29  
N 1494719.2480  
E 2418333.2970  
STA 19+00.00  
N 1494796.5910  
E 2418658.9430  
G. M. D 1765



TOWN OF BRASELTON	
OFFICE:	
BMP LOCATION DETAILS	
SR53 & SR124	DRAWING No. 54-03
INTERSECTION REALIGNMENT	