

END PROJECT  
END CONSTRUCTION  
STA 35+67.70  
N 1495660.5960  
E 2420026.5194  
LAT. 34°06'39"  
LONG. 83°45'32"

- Ds1 ALL DISTURBED AREAS WITH IN 14 DAYS OF
- Ds2 DISTURBANCE (TYP)
- Ds3 PERMANENT GRASSING


**INITIAL PHASE:**  
CONTRACTOR TO INSTALL PERIMETER FENCE PRIOR TO ALL LAND DISTURBANCE ACTIVITIES. ALL INITIAL PERIMETER FENCE SHALL BE REMOVED CONCURRENTLY WITH INTERMEDIATE MEASURES.

**INTERMEDIATE PHASE:**  
EROSION MEASURES SHALL CONSIST OF ALL BMP'S SHOWN IN THESE PLANS EXCEPT FOR Ds3. ALL DEVICES INSTALLED DURING THIS PHASE SHALL REMAIN UNTIL FINAL GRADING HAS BEEN ACHIEVED AND PERMANENT MEASURES INSTALLED.

**FINAL PHASE:**  
SHALL CONSIST OF PERMANENT GRASSING, STONE DUMPED RIP RAP FOR OUTLET PROTECTION, AND PERMANENT DITCH PROTECTION. CONTRACTOR IS TO ENSURE THAT ALL GRASS PLANTED HAS STARTED TO GROW BEFORE REMOVING TEMPORARY EROSION MEASURES.

STA 33+20.00  
N 1495576.6810  
E 2419793.9020  
  
PC STA 35+93.41  
N 1495667.8510  
E 2420051.1880

GSWCC LEVEL 1 DESIGN PROFESSIONAL NO. 0000018858  
*[Signature]*  
GEORGE A. LICENSED PROFESSIONAL  
2-25-10  
DATE



REVISION DATES	

TOWN OF BRASELTON  
OFFICE:  
**BMP LOCATION DETAILS**  
SR53 & SR124  
INTERSECTION REALIGNMENT  
DRAWING No. 54-07