



DETAIL NOTES:

1. VEGETATION REMOVAL IN THE STREAM BUFFER SHALL BE LIMITED TO THE AMOUNT NECESSARY FOR PIPELINE INSTALLATION.
2. ONCE PIPELINE INSTALLATION IS COMPLETE, STREAM BANKS AND SURROUNDING DISTURBED AREAS SHALL BE RETURNED TO ORIGINAL GRADE (NOT TO EXCEED 1:1 MAXIMUM SLOPE). RIPRAP SHALL BE INSTALLED ON THE STREAM BANKS TO THE ORDINARY HIGH WATER MARK. RIPRAP PLACED ON STREAM BANK SHALL BE HAND LAID. NO RIPRAP SHALL BE INSTALL IN STREAM BED. DISTURBED AREAS IN THE BUFFER THAT DO NOT RECEIVE RIPRAP SHALL IMMEDIATELY BE STABILIZED WITH PERMANENT GRASSING WITH EXCELSIOR MATTING.
3. CONTRACTOR TO USE DUCTILE IRON RESTRAINED JOINT PIPE UNDER CREEK BED AND A MINIMUM OF 20' PAST TOP OF BANK.

TOWN OF BRASELTON WATER & SEWER DEPARTMENTS

JOB TITLE STANDARD DETAIL	SHEET TITLE	DRN. BY: EMI	REV. NO.	BY	DATE
	MINOR CREEK CROSSING	CKD BY:	1	GKB	04-07-09
		APPD. BY:			
		DATE: MARCH 2004			
	DETAIL No. W-25	FILE No. 03033\W-25.dwg	SCALE: N.T.S.		