

February 5, 2021

ADDENDUM TO ADVERTISED CONTRACT

PROJECT NAME: REHABILITATION AND WIDENING OF
CHARDONNAY TRACE

PROJECT NUMBER: RFP #2021-01

CITY: TOWN OF BRASELTON

AMENDMENT NUMBER: 1

LETTING DATE: FEBRUARY 12, 2021

THE FOLLOWING CHANGES ARE HEREBY MADE TO THIS CONTRACT. THE BIDDER IS RESPONSIBLE FOR MAKING ANY NECESSARY CHANGES IN INK IN THE PROPOSAL. BIDDER SHALL ACKNOWLEDGE THIS AMENDMENT BY CHECKING THE APPROPRIATE SPACE ON THE AMENDMENT CERTIFICATION PAGE.

.....

QUESTIONS/CLARIFICATIONS

1. The typical sections call out poly for the 12.5mm. The pay item and summary of qty's show 12.5mm without poly. Do you have any clarification on this? **The corrected item should be "402-4510 RECYCLED ASPH CONC 12.5 MM SUPERPAVE, GP 2 ONLY, INCL POLYMER-MODIFIED BITUM MATL & H-LIME"**
2. **SEE ATTACHED REVISED BID SCHEDULE**

BID SCHEDULE

Item Number	Description	Quantity	Unit	Unit Price	Amount
ROADWAY					
150-1000	TRAFFIC CONTROL	1	LS		
210-0100	GRADING COMPLETE	1	LS		
310-1101	GR AGGR BASE CRS, INCL MATL	2387	TN		
318-3000	AGGR SURF CRS	10	TN		
402-3121	RECYCLED ASPH CONC 25 MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	1239	TN		
402-4150	RECYCLED ASPH CONC 12.5 MM SUPERPAVE, GP 2 ONLY, INCL POLYMER MODIFIED BITUM MATL & H LIME	459	TN		
402-3190	RECYCLED ASPH CONC 19 MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	417	TN		
413-0750	TACK COAT	451	GL		
432-0206	MILL ASPH CONC PVMT, 1 1/2 IN DEPTH	1767	SY		
441-0018	DRIVEWAY CONCRETE, 8 IN TK	146	SY		
441-0108	CONC SIDEWALK, 8 IN	122	SY		
441-5002	CONCRETE HEADER CURB, 6 IN, TP 2	238	LF		
441-6216	CONC CURB & GUTTER, 8 IN X 24 IN, TP 2	1357	LF		
441-6222	CONC CURB & GUTTER, 8IN X 30 IN. TP 2	176	LF		
444-1000	SAWED JOINTS IN EXIST PAVEMENTS - PCC	164	LF		
446-1100	PVMT REINF FABRIC STRIPS, TP 2, 18 INCH WIDTH	145	LF		
500-9999	CLASS B CONC, BASE OR PVMT WIDENING	2	CY		
550-1180	STORM DRAIN PIPE, 18 IN, H 1-10	236	LF		
611-8000	ADJUST CATCH BASIN TO GRADE	1	EA		
634-1200	RIGHT OF WAY MARKERS	4	EA		
668-1100	CATCH BASIN, GP 1	1	EA		
668-6112	TRENCH DRAIN, 12 IN	12	LF		
SUBTOTAL					

EROSION CONTROL

700-9300	SOD	2000	SY		
702-0000	MISC. LANDSCAPE	1	LS		
SUBTOTAL					

TEMPORARY EROSION CONTROL

163-0232	TEMPORARY GRASSING	1	AC		
163-0240	MULCH	6	TN		
163-0300	CONSTRUCTION EXIT	2	EA		
163-0550	CONSTRUCT AND REMOVE IN LET SEDIMENT TRAP	5	EA		
165-0010	MAINTENANCE OF TEMPORARY SILT FENCE, TP A	3120	LF		
165-0101	MAINTENANCE OF CONSTRUCTION EXIT	2	EA		
165-0105	MAINTENANCE OF INLET SEDIMENT TRAP	5	EA		
167-1000	WATER QUALITY MONITORING AND SAMPLING	1	EA		
167-1500	WATER QUALITY INSPECTIONS	6	MO		
171-0010	TEMPORARY SILT FENCE, TYPE A	3120	LF		
700-6910	PERMANENT GRASSING	1	AC		
700-7000	AGRICULTURAL LIME	3	TN		
700-8000	FERTILIZER MIXED GRADE	2	TN		
700-8100	FERTILIZER NITROGEN CONTENT	50	LB		
716-2000	EROSION CONTROL MATS, SLOPES	246	SY		
SUBTOTAL					

SIGNING AND MARKING

636-1033	HIGHWAY SIGNS, TP 1 MATL, REFL SHEETING, TP 9	31.50	SF		
636-1036	HIGHWAY SIGNS, TP 1 MATL, REFL SHEETING, TP 11	22.38	SF		
636-2070	GALV STEEL POSTS, TP 7	126	LF		
653-0110	THERMOPLASTIC PVMT MARKING, ARROW, TP 1	1	EA		
653-0120	THERMOPLASTIC PVMT MARKING, ARROW, TP 2	12	EA		
653-0130	THERMOPLASTIC PVMT MARKING, ARROW, TP 3	1	EA		
653-1501	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, WHITE	2924	LF		
653-1502	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, YELLOW	1504	LF		
653-1704	THERMOPLASTIC SOLID TRAF STRIPE, 24 IN, WHITE	120	LF		
653-1804	THERMOPLASTIC SOLID TRAF STRIPE, 8 IN, WHITE	450	LF		
653-0210	THERMOPLASTIC PVMT MARKING, WORD, TP 1	6	EA		
653-3501	THERMOPLASTIC SKIP TRAF STRIPE, 5 IN, WHITE	1089	GLF		
653-6004	THERMOPLASTIC TRAF STRIPING, WHITE	60	SY		
654-1001	RAISED PVMT MARKERS TP 1	50	EA		
654-1003	RAISED PVMT MARKERS TP 3	88	EA		
657-1244	PREFORMED PLASTIC SOLID PVMT MKG, 24 IN, WHITE, TP PB	67	LF		
657-5001	PREFORMED PLASTIC PAVEMENT MARKING, WHITE, TP PB	100	SY		
657-5017	PREFORMED PLASTIC PVMT MKG, WORDS/OR SYM, ARROW TP2, WHITE, TP PB	2	EA		

SUBTOTAL

SIGNAL

611-5360	RESET SIGN	2	EA		
636-1041	HIGHWAY SIGNS, TP 2 MATL REFL SHEETING, TP 9	34	SF		
639-3004	STEEL STRAIN POLE, TP IV, W/50' MAST ARM	1	EA		
647-1000	TRAFIC SIGNAL INSTALLATION – NO 1	1	LS		
682-6233	CONDUIT, NONMETL, TP 3, 2 IN	265	LF		
682-9950	DIRECTIONAL BORE – 5 IN	200	LF		
935-8000	TESTING	1	LS		
937-6050	INTERSECTION VIDEO DETECTION ASSEMBLY, TPY A	1	EA		

SUBTOTAL

TOTAL BID PRICE