

## TOWN OF BRASELTON RFB#19-1204 ADDENDUM #2

---

On page 5, under Traffic control, it states that “The contractor shall install all required striping and markings as quickly as possible, but no later than 3 days after the road is completed unless directed otherwise by the project manager.” Is this referring to temporary striping or to the final Thermoplastic as well? If it is referring to the final Thermoplastic striping and markings then Manufactures will not guarantee or warrantee this material if installed before the minimum 2 week asphalt cure period.

Response: Temporary striping is to be placed immediately after paving and before opening to traffic. Thermoplastic should be installed after the minimum cure period and around 30 days.